

Commissioning and X-ray Tube start-up recommendations

Commissioning

	kV	mA	time (mins)
<input type="checkbox"/>	20	5	5
<input type="checkbox"/>	30	5	5
<input type="checkbox"/>	40	5	5
<input type="checkbox"/>	20	10	5
<input type="checkbox"/>	30	10	5
<input type="checkbox"/>	40	10	5
<input type="checkbox"/>	20	20	5
<input type="checkbox"/>	30	20	5
<input type="checkbox"/>	40	20	5
<input type="checkbox"/>	30	30	5
<input type="checkbox"/>	40	30	5
<input type="checkbox"/>	40	40	

Start-up 0-3 days increase voltage from 20 to 40kV, 10 kV step, 1min/step
3-30 days increase voltage from 20 to 40kV, 5 kV step, 5min/step